



BVH main sewer Oberthan BL 3

Data and facts

Company

Type	Pipeline construction
------	-----------------------

Runtime	05.2017 - 12.2017
---------	-------------------

Principal	EWV AG Abteilung Wasser
-----------	-------------------------

[Project report online](#)

www.porr-group.com



New main sewer for Wels.

Scope of services in detail:

Reinforced concrete/ovoid profile DN1000/1500 laid: 820m approx.

Reinforced concrete pipes DN1000 laid: 200m approx.

Reinforced concrete pipes DN700 laid: 130m approx.

Total excavated volume: 15,000m³ approx.

Gravel 4/8mm: 4,000m³ approx.

Invert concrete: 450m³ approx.

Impressions



Image notes

1

Challenging conditions

The PORR team shifted around 15,000m³ of excavated soil in often challenging and loose soil conditions.

Do you have questions about the project or would you like to learn more? Feel free to contact us for further information.

PORR AG Group Communications

Absberggasse 47

1100 Wien

T +43 50 626-0

E-Mail: comms@porr-group.com