



## Conversion of the roundabout at B50/S4 – Mattersburg Arena

### Data and facts

Company	ÖBA – Österreichische Betondecken Ausbau GmbH
Type	Concrete slab construction
Principal	Held & Francke Baugesellschaft m.b.H.

[Project report online](#)

[www.porr-group.com](http://www.porr-group.com)

**PORR**

# Working without traffic jams.

The construction project was implemented in various traffic stages and construction sections within only three months. In the process, traffic was hardly restricted at all. The concrete slab covers an area of 1,500 m<sup>2</sup> and is 25 cm thick. The work package also included all of the joint works, and the concrete slab being manufactured by hand. This facilitated the implementation of the project, because it allowed the construction phases to be selected much more flexibly.

## Impressions



## Image notes

1

Construction works without traffic jams.

The busy section of road remained open to traffic throughout the entire construction time.

2

Working by hand for more flexibility.

The installation by hand of the concrete slabs helped the project planners to have more flexibility.

3

The final touch.

Before the concrete hardens, the surface is smoothed by hand with a polishing knife, and the brushstrokes are created.

Do you have questions about the project or would you like to learn more? Feel free to contact us for further information.

**PORR AG Group Communications**

Absberggasse 47

1100 Wien

T +43 50 626-0

E-Mail: [comms@porr-group.com](mailto:comms@porr-group.com)